

CONTRACT NO. QA2985177

FAP NO. AC-STBG-G-295-1(10)E

MD 213 LIBERTY ST & COMMERCE ST FROM MILL STREAM BR TO GRAVEL RUN IN CENTREVILLE, SAFETY & RESURFACING

BID DATE: 01/16/20, TIME: 06/30/20, LD'S \$740/CAL DAY, MBE 8%, INCLUDES ADDENDUM 1

ITEM	QTY	UNIT	DESCRIPTION	UNIT PRICE	TOTAL PRICE
1001	1	LS	CLEARING & GRUBBING		
1002	1	LS	TY B ENGINEERS OFFICE		
1003	3,000	EA	PRICE ADJUSTMENT FOR DIESEL FUEL	\$ 1.00	
1004	7,500	LF	5" YELLOW PVMNT MRKG PAINT		
1005	18,000	LF	5" WHITE PVMNT MRKG PAINT		
1006	900	LF	12" WHITE PVMNT MRKG PAINT		
1007	700	LF	24" WHITE PVMNT MRKG PAINT		
1008	7,500	LF	5" YELLOW REMOVABLE PVMNT LINE MRKGS		
1009	18,000	LF	5" WHITE REMOVABLE PVMNT LINE MRKGS		
1010	900	LF	12" WHITE REMOVABLE PVMNT LINE MRKGS		
1011	700	LF	24" WHITE REMOVABLE PVMNT LINE MRKGS		
1012	27,100	LF	REMOVAL OF REMOVABLE PVMNT MRKG LINES - ANY WIDTH		
1013	10,000	LF	REMOVAL OF EXISTING PVMNT LINE MRKGS ANY WIDTH		
1014	1	LS	MAINTENANCE OF TRAFFIC		
1015	50	TON	ASPHALT FOR MAINTENANCE OF TRAFFIC		
1016	50	UD	ARROW PANEL		
1017	300	SF	TEMP TRAFFIC SIGNS HIGH PERF WIDE ANGLE RETROREFL SHTG		
1018	1,600	HR	FLAGGER		
1019	250	EA	DRUMS FOR MAINTENANCE OF TRAFFIC		
1020	100	UD	PORTABLE VARIABLE MESSAGE SIGN		
1021	20	UD	PROTECTION VEHICLE		
1022	1	LS	CONSTRUCTION STAKEOUT		
1023	1	LS	MOBILIZATION & DEMOBILIZATION		
2001	14	CY	REMOVAL OF EXISTING SIDEWALK		
5001	20	TON	SP ASPHALT MIX 9.5MM FOR WEDGE/LEVEL PG 64S-22 L2		
5002	3,415	TON	SP ASPHALT MIX 12.5MM FOR SURFACE HDFV PG 64S-22 L2		
5003	320	TON	SP ASPHALT MIX 19.0MM FOR FULL-DEPTH PATCH PG 64S-22 L2		
5004	5,000	EA	PRICE ADJUSTMENT FOR ASPHALT BINDER	\$ 1.00	
5005	9,000	EA	PAYMENT ADJUSTMENT FOR PVMNT DENSITY	\$ 1.00	
5006	9,000	EA	PAYMENT ADJUSTMENT FOR ASPHALT MIXTURE	\$ 1.00	
5007	29,025	SY	FINE MILLING ASPHALT PVMNT 1" TO 2.5" DEPTH		

5008	10,650	LF	5" WHITE THERMO PVMNT MRKGS		
5009	7,800	LF	5" YELLOW THERMO PVMNT MRKGS		
5010	810	LF	12" WHITE PRFRMD THERMO PVMNT MRKG LINES		
5011	810	LF	24" WHITE PRFRMD THERMO PVMNT MRKG LINES		
5012	140	SF	WHITE PRFRMD THERMO PVMNT MRKG LEGENDS & SYMBS		
5013	50	CY	REMOVAL OF UNSUITABLE MATERIAL & REFILL		
5014	45	SF	BIKE LANE PRFRMD THERMO PVMNT MRKG WITH ARROW		
5015	130	SF	SHARED BIKE LANE PRFRMD THERMO PVMNT MRKG		
6001	276	LF	STD TY A CURB 8" X 16" MIN		
6002	688	LF	STD TY A COMB CURB & GTR 12" GTR PAN 8" MIN DEPTH		
6003	1,890	SF	5" CONCRETE SIDEWALK		
6004	183	SF	DETECTABLE WARNING SURFACE FOR CURB RAMPS		
6005	77	SF	DETECTABLE WARNING SURFACE USING BRICK PAVERS		
6006	929	SF	BRICK SIDEWALKS		
7001	60	SY	PLACING FURNISHED TOPSOIL 4" DEPTH		
7002	60	SY	REFERTILIZING		
7003	60	SY	TURFGRASS SOD ESTABLISHMENT		
8001	9	EA	SQUARE PERFORATED TUBULAR STEEL SIGN POSTS		
8002	9	EA	SQUARE TUBULAR STEEL ANCHOR BASES		
8003	70	SF	SHEET ALUMINUM SIGNS		
8004	70	SF	INSTALL GROUND MOUNTED SIGN		
TOTAL PRICE					