

CONTRACT NO. DO2035180**FAP NO.: N/A****RPLMNT OF SM STRUC NO. 09045X0 DOUBLE 36" RCP ON MD 331 (RHODESDALE RD) CARRYING A TRIBUTARY OF NANTICOKE RIVER****DORCHESTER CO, BID DATE: 01/21/19. 6% MBE, CONTRACT TIME 08/31/20, LD'S \$580/CAL DAY**

ITEM	QTY	UNIT	DESCRIPTIONS	UNIT PRICE	TOTAL PRICE
1001	1	LS	CLEARING & GRUBBING		
1002	1,000	EA	PRICE ADJUSTMENT FOR DIESEL FUEL	\$ 1.00	\$ 1,000.00
1003	100	LF	5" YELLOW REMOVABLE PAVEMENT LINE MRKGS		
1004	100	LF	5" WHITE REMOVABLE PAVEMENT LINE MRKGS		
1005	1	LS	MAINTENANCE OF TRAF		
1006	150	TON	GRADED AGGREGATE BASE FOR MAINTENANCE OF TRAF 120562		
1007	75	TON	ASPHALT FOR MAINTENANCE OF TRAF		
1008	385	SF	TEMP TRAF SIGNS HI PERF WIDE ANGLE RETROREFLECTIVE SHTG		
1009	285	LF	RESET PRECAST TEMP CONC TRAF BARR FOR MOT		
1010	10	EA	REFLECTIVE BARR MARKERS		
1011	4	EA	TYPE III BARRICADE FOR MAINTENANCE OF TRAF		
1012	2	EA	VERTICAL PANELS		
1013	140	EA	DRUMS FOR MAINTENANCE OF TRAF		
1014	40	UD	PORTABLE VARIABLE MESSAGE SIGN		
1015	20	UD	PROTECTION VEHICLE		
1016	2	EA	TEMP TYPE E TRAF BARR END TRMNT FOR 50 MPH ANY WDTN		
1017	2	EA	REM & RES TEMP TYPE E TRAF BARR END TRMNT ANY BAYS ANY WDTN		
1018	380	LF	PRECAST TEMP 32" F SHAPE CONC TRAF BARR		
1019	1	LS	CONSTRUCTION STAKEOUT		
1020	1	LS	MOBILIZATION AND DEMOBILIZATION		
2001	260	CY	SELECT BACKFILL FOR 36" REINFORCED CONC PIPE		
2002	825	CY	CLASS 1 EXCAVATION		
2003	10	CY	CLASS 1-A EXCAVATION		
2004	3	CY	TEST PIT EXCAVATION		
3001	230	CY	AGGREGATE BEDDING AND BACKFILL USING #57 STONE		
3002	12	CY	GRADED AGGREGATE BASE BENEATH HEADWALLS		
3003	1	LS	DOWNSTREAM HEADWALL FOR SMALL STRUC NO09045X0		
3004	1	LS	REMOVAL AND DISPOSAL OF EXISTING CMP		
3005	1	LS	UPSTREAM HEADWALL FOR SMALL STRUC NO09045X0		
3006	260	LF	36" REINFORCED CONC PIPE CLASS V		
3007	2	EA	SUMP PIT		
3008	49	LF	DIVERSION FENCE		
3009	55	SY	CLASS I RIPRAP FOR SLOPE AND CHANNEL PROTECTION		

3010	30	TON	RIPRAP FOR SEDIMENT CONTROL		
4001	1	LS	REMOVAL OF EXISTING STEEL TRAF PLATES		
4002	1	LS	SALVAGING EXISTING STEEL TRAF PLATES		
4003	1	LS	MAINTENANCE OF STREAM FLOW		
5001	10	TON	SP ASPHALT MIX 9.5MM FOR WEDGE/LPG 64S-22L2		
5002	220	TON	SP ASPHALT MIX 12.5MM FOR SURFACE PG 64S-22 L2		
5003	110	TON	SP ASPHALT MIX 25.0MM FOR BASE PG 64S-22 L2		
5004	1,000	EA	PRICE ADJUSTMENT FOR ASPHALT BINDER	\$ 1.00	\$ 1,000.00
5005	1,000	EA	PAYMENT ADJUSTMENT FOR PAVEMENT DENSITY	\$ 1.00	\$ 1,000.00
5006	1,000	EA	PAYMENT ADJUSTMENT FOR ASPHALT MIXTURE	\$ 1.00	\$ 1,000.00
5007	1,000	SY	FINE MILLING ASPHALT PAVEMENT 1" TO 2.5" DPTH		
5008	730	SY	6" GRADED AGGREGATE BASE COURSE		
6001	50	LF	STANDARD TYPE A CURB 8" X 16" MINIMUM		
6002	75	LF	TRAF BARR W BEAM USING 8 FOOT POST		
6003	75	LF	REM & DISP OF EXISTING TRAF BARR W BEAM		
6004	2	EA	W BEAM BARR REFLECTIVE DELINEATORS		
7001	300	SY	PLACING FURNISHED TOPSOIL 2" DPTH		
7002	550	SY	PLACING FURNISHED TOPSOIL 4" DPTH		
7003	220	SY	TEMP SEED		
7004	2,800	SY	TEMP MULCH		
7005	850	SY	TURFGRASS ESTABLISHMENT		
7006	850	SY	REFERTILIZING		
8001	40	LF	WOOD SIGN SUPPORTS 4" X 4"		
8002	30	SF	SHEET ALUMINUM SIGNS		
8003	155	LF	NO4 AWG STRANDED BARE COPPER GROUND WIRE		
8004	135	LF	DUCT CABLE - 6 CONDUCTOR NO4 AWG		
8005	1	EA	FURNISH AND INSTALL ELECTRICAL MANHOLE		
8006	20	LF	DUCT CABLE - 2 CONDUCTOR NO 4 AWG 600 V		
8007	8	EA	CONNECTOR KIT - TYPE I		
8008	2	EA	CONNECTOR KIT - TYPE III		
8009	4	EA	CONNECTOR KIT - TYPE IV		
TOTAL PRICE					